FLOYD COUNTY SCHOOLS
ENGAGE - EMPOWER - EQUIP
Every - Child - Every - Day

SUPERINTENDENT
TONYA HORNE-WILLIAMS

BOARD CHAIR DISTRICT 1
LINDA GEARHEART

MEMBER DISTRICT 2
DR. CHANDRA VARIA

MEMBER DISTRICT 5
STEVE SLONE

VICE CHAIR DISTRICT 4
KEITH SMALLWOOD

MEMBER DISTRICT 3
WILLIAM NEWSOME, JR

Consent Agenda Item (Action Item): Consider/Approve advertising for competitive bids for the **Prestonsburg High School Parking Lot and Flood Wall Project**.

Applicable State Regulations: 702 KAR 4:160 – Capital Construction Process and applicable Board policies and procedures.

Fiscal/Budgetary Impact: The project will be competitively bid, and the final project cost will be determined through the bidding process. Funding will be identified and confirmed prior to the award of the contract.

History/Background: The parking lot at Prestonsburg High School sustained significant damage due to erosion and flooding. The existing concrete parking area and adjacent curb have been damaged and require removal and replacement. The project is intended to restore the parking area and provide additional protection against future flooding and erosion.

Project Scope:
The project will include, but is not limited to, the following work:

- Remove and dispose of approximately **210 feet by 24 feet by 6 inches** of existing concrete parking lot.
- Remove approximately **210 linear feet of 3-foot-wide, 6-inch-thick concrete curb** that was damaged due to erosion from flooding.
- Haul off and properly dispose of all removed and broken concrete.
- Construct and pour approximately **210 feet by 24 feet by 6 inches** of new concrete parking lot slab.
- Reinforce the new concrete parking lot slab with rebar installed on **12-inch centers**.
- Construct and pour a new approximately **4-foot-high by 210-foot-long by 12-inch-thick flood wall**.
- Construct a concrete footing for the flood wall measuring approximately **210 feet by 2 feet by 12 inches**.
- Install rebar dowels at **12-inch centers** within the flood wall footing.
- Dowell the flood wall reinforcement into the new concrete parking lot slab to provide additional structural reinforcement and stability.
- Provide all necessary labor, materials, equipment, excavation, hauling, disposal, forming, reinforcement, concrete placement, and related work necessary to complete the project.

Recommendation: It is recommended that the Floyd County Board of Education approve advertising for competitive bids for the **Prestonsburg High School Parking Lot and Flood Wall Project** in accordance with applicable Kentucky statutes, regulations, and Board policies. Upon receipt and evaluation of bids, the project will be presented to the Board for consideration of contract award.

Kevin O'Quinn
Director

Tonya H. Wille
Superintendent

Date: October 5, 2026

The Floyd County Board of Education does not discriminate on the basis of race, color, national origin, age, religion, marital status, sex, or disability in employment, educational programs, or activities as set forth in Title IX & VI, and in Section 504.